



Wind Diesel Hybrid Design Experience

6 Years of Ascension Island Wind Farm Operations

Shawn West/Gary Seifert
INEEL

September 2001

Background information



Background information



Background information



Background information

- ***Air Force power generated by a prime power diesel-electric plant***
- ***Air Force load averages 2.2 to 2.4 MW***
- ***Two 1900 kW diesel generators operate in parallel with the wind farm***
- ***Waste engine heat powers the desalination system***



12/3/1998



12/3/1998



12/3/1998

Construction

- ***Project funded through AF Energy Conservation Investment Program (ECIP)***
- ***Designed by DOE's Idaho National Engineering and Environmental Laboratory***
- ***Prime contractor was joint venture between Pacific Industrial Electric and Difko Administration (US) Inc.***
- ***Concept to construction complete - in 45 months***
- ***Awarded Sept 95 with a 540 day performance period***
- ***Project completed Sept 96 - 6 months ahead of schedule***

Long History of Wind On Ascension



The Wind farm at Ascension



CHALLENGES



- ***Remote shipping - 5000 miles from Port Canaveral***
- ***Restricted shipping schedules***
- ***Pier restrictions***
- ***Limited crane reach***
- ***Limited island access***

Other Possibilities



*Just remember
anything that
could go wrong
probably will*

Planning is Key!



The Team

Background Information



- *Four three-bladed 225 kW MICON wind turbines for a total of 900 kW*
- *Average Ascension wind speed: 7.8 m/s (17.5 mph)*
- *4 Up-wind Micon Turbines (40/225kW EA.)*
- *30m Tower Height (Hub)*
- *Fixed Pitch Stall Regulated*
- *29.8 m Rotor Diameter*

Background Information

- ***The wind farm supplements the diesel power plant***
- ***4 year simple payback***
- ***Average wind power output is 342 kW***
 - ***38% capacity factor***
- ***To meet base electrical load the power plant operates two 1900 kW generators creating a low load factor on the generators***
- ***One generator operation less stable***

PERFORMANCE

- ***19,200,000 kWhrs Between Oct 96 And Sept 02***
- ***Downtime between 89 hours 489 hours per year***
- ***>97% Availability***
- ***Replaced one gear box, transformer, varistor, breaker, and many mounting plates***
- ***Corrosion control a challenge***
- ***Saved 1,440,000 gallons of fuel to date***
- ***Significant Nox and CO reduction***

Corrosion Control is a Challenge



Site Approval & Environmental

- ***Site approval***
 - ***Location required negotiating a lease***
 - ***Involving island administrator early on was important***
- ***Environmental***
 - ***Two main issues***
 - ***Bird strikes***
 - ***Electro-magnetic interference***
 - ***Land animals were not an issue***

LESSONS LEARNED

- ***Perform resource assessments***
- ***Mandatory job walk essential***
- ***Partner with the teams at the beginning***
- ***Performance based specifications***
- ***Conquer corrosion control***
- ***Work the load management into the control systems for stability***
- ***Establish maintenance contract***
- ***Plan and model loads up front***
- ***Wind/Diesel systems are very compatible***

Follow-on Project

- ***Description***
 - ***1800 kW (2 Micon 900 turbines)***
 - ***Electric boiler for grid stability and fresh water production***
- ***Schedule***
 - ***Design and Bidding complete***
 - ***400-700 day construction period***
 - ***Contract award Sept 02***
 - ***Swanson (from Anchorage) is the Prime***

Before



Thanks to;

Craig Miller

Peterson AFB, Co.

Jeff Leslie

45 SP Wing

Patrick AFB, Fla.



After